

(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
PROJECT OFFICE, T.R. PATTINAM 609 606, KARAIKAL.

Phone: 04368-233060, 233344

Email: ppclmmc@gmail.com

Telefax: 04368-233355

Ref.No: R-023/MMC/2019-20/ 1739

Dated: 24.10.2019

GSTIN No.34AAACP6507E1ZS

ENQUIRY

To

Sub: Inviting offer for Power Cable Laying Work in Residential Quarters- Reg.

QUOTATION TO BE

Submitted on or before 21.11.2019 @ 05.00 PM	Opened on 22.11.2019 - 3.00 PM
Kept valid for 3 months from the date of opening	Submitted in TWO parts

Wax Sealed quotations are invited for carrying out the Power Cable Laying Work in the PPCL Residential Quarters as per the scope of work enclosed in the annexure and as per our terms and conditions mentioned therein.

Scope of Work:

- Earth work excavation 0.75mt(D)x0.304mt(W) x 340mts (L) (Approximately)
- Earth work excavation at metal road crossing & drainage 0.75mt (D) x 0.304mt(W) x 20mts.(L)(Approximately)
- Providing 2" GI pipe (B-class) at road & drainage crossing, wherever GI clamps required - 30mts (L) (Approximately)
- Material required - river sand (0.075mt (D) X 0.304 mt(L) & bricks for laying - 360mts(L) Approximately.
- Refilling of excavated soil
- Laying of 50 sq.mm aluminum cable - **290 mts (L)** approximately.
- Laying of 25 sq.mm aluminum cable - **110 mts (L)** approximately.

TERMS AND CONDITIONS:

- The rate quoted should be firm and inclusive of GST, ESI & EPF, manpower, materials, tools and tackles, etc. required for the works, and all other charges.
- The Party should have previous work experience in the field of LT cable laying and termination work in any industries or government Organizations and should produce the supporting documents for the same at the time of submitting the offer.**
- The Work should be carried out in PPCL Residential Quarters as per the directions of the Engineer-in-Charge.
- The party may visit our site to assess the job before submitting the offer.
- The L1 bidder shall be arrived as the lowest bidder for total amount for all the items.

6. **100%** Payment will be made within 30 days from the date of receipt of your invoice after completion of work satisfactorily and approval of Engineer-in-charge and after submission of EPF/ESI, etc. & other statutory compliances. Otherwise **80%** payment will be made after completion of work satisfactorily and approval of Engineer-in-charge and the balance **20%** payment will be made after submission of necessary EPF, ESI, etc. documents. **The bill in Triplicate along with advance stamped receipt should be sent to the undersigned for effecting payment.**
7. **EARNEST MONEY DEPOSIT:** An Earnest Money Deposit for an amount of **Rs.2400/-** should be paid by demand draft drawn in favour of the SUPERINTENDING ENGINEER, Puducherry Power Corporation Ltd T.R. Pattinam, Karaikal on any Nationalized/Schedule bank payable at Karaikal. The earnest money deposit will bear no interest and will be released for the unsuccessful bidders after placing the order to the successful bidder. The EMD of the successful bidder shall be returned after completion of work and acceptance.
8. Parties registered with NSIC or SSI/MSME is exempted for submitting EMD/SD. However copies of supporting Documents/Certificates should be kept in separate cover super scribing **“Earnest Money Deposit Exemption”**.
9. The party shall be required to place the earnest money and the tender in separate sealed envelopes marked “Earnest Money” and “Tender” respectively. Both the envelopes shall then be placed in another sealed envelope and submitted to the tender inviting authority in the usual manner. The officer opening the tenders shall first open the envelope containing the earnest money. If the earnest money is found to be in order, only then the Officer shall proceed further with opening the tender.
10. Payment will be made only after submission of the following :
- **For EPF:**
To be generated from the EPF website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.
 - i. Combined challan of account no.01, 02, 10, 21 &22 with TPRN number.
 - ii. EPF-Electronic Challan cum Return (ECR)
 - iii. EPF Challan summery/EPF-TRPN details.
 - **For ESI:**
To be generated from the ESI website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.
 - i. ESI challan number
 - ii. ESI monthly contribution –online challan status (Transaction details)
 - iii. ESI monthly contribution (Contractor wise) for the month of.....

(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

PROJECT OFFICE, T.R. PATTINAM 609 606, KARAIKAL.

Phone: 04368-233060, 233344

Email: ppclmmc@gmail.com


Telefax: 04368-233355

Ref.No: R-023/MMC/2019-20/ 1739

Dated: 24.10.2019

GSTIN No.34AAACP6507E1ZS

11. Party should obtain all permits and licenses under the laws or regulations applicable and in connection with the work carried out and shall comply with and discharge all statutory obligations/liabilities under the various laws such as Factory Act/Workmen's Compensation Act /Employee's State Insurance Act / Employee's Provident Fund Act / Payment of Wages Act / Contract Labour (Regulation & Abolition) Act / Minimum Wages Act Etc., or any modification thereof.
12. Necessary Gate pass should be obtained well before the commencement of work. The party should submit two copies of photographs of all the employees deployed in PPCL for the above work for gate pass purpose. The name & photo of the employees should be attested by the contractor.
13. All the Safety Rules as per the Factory Act 1948, Puducherry Factory Rule and PPCL Safety instructions to be strictly followed inside the plant area. In case of any faulty workmanship in the scope of work the party must rectify the same Otherwise the estimated amount will be deducted in your work bill.
14. The contractor should provide helmets & safety shoes for all the employees engaged to be working in PPCL Residential Quarters.
15. The work should be completed within the time as scheduled in the work order.
16. In case of any faulty workmanship in the scope of work, the tenderer must rectify the same on free of Cost.
17. Our Tax payment Identification **GSTIN No.34AAACP6507E1ZS** is registered with Commercial Taxes Department, Puducherry.
18. Sealed quotation should be superscripted as "QUOTATION / ENQUIRY NO. **R-023 for Power Cable laying work.** Quotation is to be sent with superscription, wax sealed. The quotations through fax/mail and received after the due date shall not be considered.
19. If the tender opening date happens to be a holiday, the tender will be opened on the next working day.
20. The undersigned reserves all rights to accept/reject any or all the quotations without assigning any reasons thereof.


24/10/2019**EXECUTIVE ENGINEER (MECH.)-PLANT**

ENQUIRY PAGE - 4

Sl. No.	Description	Qty In Mtrs	Rate/Qty (in Rs.)	Amount (Rs.)
1	Earth work excavation 0.75mt(D)x0.304mt(W) x 340mts (L) (Approximately)			
2	Earth work excavation at metal road crossing & drainage 0.75mt (D) x 0.304mt(W) x 20mts.(L) (Approximately)			
3	Providing 2" GI pipe (B-class) at road & drainage crossing, wherever GI clamps required - 30mts (L) (Approximately)			
4	Material required - river sand (0.075mt (D) X 0.304mt (L) & bricks for laying - 360mts (L) Approximately.			
5	Refilling of excavated soil (Lumpsum)			
6	Laying of 50Sq.mm aluminium cable (Length Approx)	290		
7	Laying of 25Sq.mm Alminium Cable (Length Approx)	110		
Sub-Total				
Add: Transportation charges@ %				
GST @ %				
Total Amount (Rs.)				

Commercial Terms and Condition:

Sl No.	Details	Terms in Enquiry	Terms Accepted by the Party
1	Price Quoted	Inclusive of manpower, transport charges, GST, ESI & EPF charges, excavation and refilling charges and other charges.	
2	Payment Terms	80% Payment within 30days after completion and balance 20% after submission of ESI & EPF documents	
3	Validity	90 Days from date of opening	
4	Delivery/ Completion Period	To be completed as per the directions of the Engineer-in-charge.	
5	Acceptance of All the Terms and Conditions	To be Accepted	

Signature with Seal of the Party