



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
T.R. PATTINAM - 609606, KARAIKAL.



Phone No: 04368- 233060

E-Mail: ppclmmc@gmail.com

Our GSTIN No.: 34AAACP6507E1ZS

Dt. 04.04.2025

Ref. No: AC-004/MMC/2025-26/ 46

ENQUIRY

To

As per list enclosed.

Sub: Inviting offer for Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL, T.R.Pattinam, Karaikal - Reg.

QUOTATION TO BE:

Submitted on or before 08.04.2025 - 12.00 PM	Opened on 08.04.2025 -03.00PM
Kept valid upto three months	Submitted in one part.


Sealed quotations are invited for "Inviting offer for Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL, Karaikal " as per the scope of work furnished in the annexure and as per our terms and conditions mentioned therein.

TERMS AND CONDITIONS:

1. The rate quoted should be inclusive of Skilled manpower, all tools and tackles, machineries, safety equipments etc. required for the works, all taxes, EPF & ESI charges and other charges as admissible. **GST Compliance will be made as per the latest GOI orders.**
2. 100% Payment will be made within 30 days from the date of receipt of your invoice after completion of work satisfactorily and approval of Engineer-in-charge and after submission of EPF/ESI, etc. documents. Otherwise 80% payment will be made after completion of work satisfactorily and approval of Engineer-in-charge and the balance 20% payment will be made after submission of necessary EPF & ESI, etc. documents.
3. The bill in triplicate along with advance stamped receipt should be sent to the undersigned for effecting payment.
4. The L1 position shall be arrived on total amount quoted basis for completing the entire scope of work furnished in the annexure. All items have to be quoted for measurement of work.
5. The Contractor / Agency awarded with work order shall make payments for ESI & EPF in separate code number other than PPCL code. No permission shall be given for PPCL code.
6. Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work to be completed at the earliest within two days only. Extension will not be given further. L1 bidder has to mobilize before plant stoppage.



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
T.R. PATTINAM - 609606, KARAİKAL.



Phone No: 04368- 233060

E-Mail: ppclmmc@gmail.com

Our GSTIN No.: 34AAACP6507E1ZS

Dt. 04.04.2025

Ref. No: AC-004/MMC/2025-26/46

Page No.2

7. The contractor should submit the following:

For EPF:

To be generated from the EPF website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.

- i) Combined challan of account no. 01,02,10,21 & 22 with TRRN number.
- ii) EPF - Electronic Challan cum Return (ECR) iii) EPF Clallan summery/ EPF - TRRN details

For ESI:

To be generated from the ESI website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.

- i) ESI challan number ii) ESI monthly contribution- online challan status (Transaction details)
- iii) ESI monthly contribution details (contractor wise) for the month of.....

And other records to be submitted along with the above:


Copy of register of wages for the persons deployed to PPCL duly attested by the contractor.

Copy of register of muster roll/attendance for the persons deployed to PPCL duly attested by the contractor.

Copy of payment proof for the persons deployed to PPCL through bank duly attested by the contractor.

In addition to the above as a mandatory, the proposed parties/manpower supply contractors have to obtain the FORM-III -Registration certificate under Pondicherry shops and Establishment Rules 1964 as a Employer of the Establishment to be permitted to employ persons under their firm and also obtain Labour License under the contract labour (Regulation & Abolition act. 1970 with the labour Department, Government of Puducherry, Karaikal.

8. Necessary Gate pass should be obtained well before the commencement of work.
9. All the Safety Rules as per the Factory Act 1948, Puducherry Factory Rule and PPCL Safety instructions to be strictly followed inside the plant area.
10. In case of any faulty workmanship in the scope of work, the tenderer must rectify the same. Otherwise the estimated amount will be deducted in your work bill.
11. Our GSTIN No.: 34AAACP6507E1ZS registered with Commercial Taxes Department, Puducherry.
12. Sealed quotation should be superscripted as "QUOTATION / ENQUIRY No.AC-004 - Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL, Karaikal - due on 08.04.2025".
13. Applicable other charges, if any should be clearly mentioned as whether inclusive or exclusive. If not mentioned, it will be presumed that the rate quoted is inclusive of all taxes other charges.
14. The party should submit two copies of photographs of all the employees deployed in PPCL for the above work for gate pass purpose. The name & photo of the employees should be attested by the contractor.
15. The undersigned reserves all rights to accept/reject any or all the quotations without assigning any reasons thereof.


04/04/2025

EXECUTIVE ENGINEER(MECH)-PLANT



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
T.R. PATTINAM - 609606, KARAIKAL.



Phone No: 04368- 233060

E-Mail: ppclmmc@gmail.com

Our GSTIN No.: 34AAACP6507E1ZS

Dt. 04.04.2025

Ref. No: AC-004/MMC/2025-26/ 46

ANNEXURE Page No.1

Scope of work

Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL SITE, Karaikal.


1. Gas Turbine Generator cooler #5 blind plates to be removed inside/outside duct to be cleaned/ inspected and painting has to be carried out. If required, necessary repairing work has to be carried out.
2. Gasket preparation, fixing of Gaskets and inserting the new tube bundle in position #5 as per the instruction of Engineer- in Charge.
3. After fixing cooler bundle, its cooling water inlet and outlet pipelines/fittings are to be re-fixed as per the existing system.
4. During the execution of the above work, if modification required for proper fixing the new cooler, during connecting the pipelines, etc. necessary welding, cutting to be carried out.
5. After assembling work, tightness checking of water side/ air side.
6. Generator cooler#2, cooling water line inlet and outlet valves to be replaced by new.
7. After charging of cooling water, if any water leakages in the system, i.e to be attended.
8. The ACW pump #1 discharge valve and its NRV replacement work.
9. Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work to be completed at the earliest within two days only. Extension will not be given further. L1 bidder has to mobilize before plant stoppage.
10. The rate should be quoted in lump sum basis.
11. Fulfillment of all statutory obligations like ESI, PF, and other pertaining to you/employees for execution of the job.

04/04/2025

EXECUTIVE ENGINEER(MECH)-PLANT



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
T.R. PATTINAM - 609606, KARAIKAL.



Phone No: 04368- 233060

E-Mail:ppclmmc@gmail.com

Our GSTIN No.: 34AAACP6507E1ZS

Ref. No: AC-004/MMC/2025-26/ 46

Dt. 04.04.2025

ANNEXURE Page No.2

Name Of Work: Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL SITE, Karaikal.

Sl. No	Description	Amount in Rs.
	Charges towards the Installation of New Tube bundle in the GTG Air Cooler# 5, Cooling water inlet outlet valves replacement and ACW Pump#1 discharge valve and NRV replacement work at PPCL SITE, Karaikal.	
1.	1. Gas Turbine Generator cooler #5 blind plates to be removed inside/outside duct to be cleaned/ inspected and painting has to be carried out. If required, necessary repairing work has to be carried out. 2. Gasket preparation, fixing of Gaskets and inserting the new tube bundle in position #5 as per the instruction of Engineer- in Charge. 3. After fixing cooler bundle, its cooling water inlet and outlet pipelines/ fittings are to be re-fixed as per the existing system. 4. During the execution of the above work, if modification required for proper fixing the new cooler, during connecting the pipelines, etc. necessary welding, cutting to be carried out. 5. After assembling work, tightness checking of water side/ air side. 6. Generator cooler#2, cooling water line inlet and outlet valves to be replaced by new. 7. After charging of cooling water, if any water leakages in the system, i.e to be attended. 8. The ACW pump #1 discharge valve and its NRV replacement work.	
	Transportation charges, ESI & EPF Charges, all tools and tackles, Machineries	Inclusive
2.		GST @ 18%
3.		Total Amount in Rs.

Payment Terms: As per Terms & Condition - 2

Validity: Your offer should be valid for 90 days from the date of tender opening.

Note: 1) The rates to be quoted in all the columns of the above schedule and no columns should be left blank, if any column is left blank then the offered quotation will not be considered.

2) The quoted schedule should be affixed by the company seal and signed by the concerned authority.

Name of the Company:

Company seal with Signature: