



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

T.R. PATTINAM – 609606, KARAİKAL.



Phone No:04368- 233060

E-Mail : ppclmmc@gmail.com

Fax: 04368 - 233355.

Our GSTIN No.: 34AAACP6507E1ZS

Ref. No: AB-062/MMC/2024-25/ 1244

Dt. 07.10.2024

ENQUIRY

To

As per list enclosed.

Sub: Inviting offer for “Replacement Work of Cooling Tower Fan 1 & 2 FRP support structures during the Annual maintenance shutdown for the year 2024 as per scope of work attached” at PPCL Site, T.R.Pattinam, Karaikal – Reg.

QUOTATION TO BE:

Submitted on or before 29.10.2024 - 12.00 PM	Opened on 30.10.2024 -03.00PM
Kept valid up to three months	Submitted in One Part

Wax Sealed quotations are invited for “Replacement Work of Cooling Tower Fan 1 & 2 FRP support structures during the Annual maintenance shutdown for the year 2024 as per scope of work attached” at PPCL site, T.R.Pattinam, Karaikal.

TERMS AND CONDITIONS:

1. The rate quoted should be inclusive of manpower, tools and tackles, etc. required for the works, **GST, EPF & ESI charges and other charges** as admissible.
2. 100% Payment will be made within 30 days from the date of receipt of your invoice after completion of work satisfactorily and approval of Engineer-in-charge and after submission of EPF/ESI, etc. documents. Otherwise 80% payment will be made after completion of work satisfactorily and approval of Engineer-in-charge and the balance 20% payment will be made after submission of necessary EPF & ESI, etc. documents.
3. The bill in triplicate along with advance stamped receipt should be sent to the undersigned for effecting payment.
4. The contractor should submit the following:

For EPF:

To be generated from the EPF website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.

i) Combined challan of account no. 01,02,10,21 & 22 with TRRN number.

ii) EPF – Electronic Challan cum Return (ECR)

iii) EPF Clallan summery/ EPF - TRRN details



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

T.R. PATTINAM - 609606, KARAIKAL.

Phone No:04368- 233060

E-Mail : ppclmmc@gmail.com

एक कदम स्वच्छता की ओर

Fax: 04368 - 233355.

Our GSTIN No.: 34AAACP6507E1ZS

Dt. 07.10.2024

Ref. No: AB-062/MMC/2024-25/ 10 11

ENQUIRY PAGE NO. 2

For ESI:

To be generated from the ESI website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.

- i) ESI challan number ii) ESI monthly contribution- online challan status (Transaction details)
iii) ESI monthly contribution details (contractor wise) for the month of.....

And other records to be submitted along with the above:

Copy of register of wages for the persons deployed to PPCL duly attested by the contractor.
Copy of register of muster roll/attendance for the persons deployed to PPCL duly attested by the contractor.

Copy of payment proof for the persons deployed to PPCL through bank duly attested by the contractor.

In addition to the above as a mandatory, the proposed parties/manpower supply contractors have to obtain the FORM-III -Registration certificate under Pondicherry shops and Establishment Rules 1964 as a Employer of the Establishment to be permitted to employ persons under their firm and also obtain Labour License under the contract labour (Regulation & Abolition act. 1970 with the labour Department, Government of Puducherry, Karaikal.

5. ESI/EPF to be submitted in separate code and PPCL code shall not be given.
6. Necessary Gate pass should be obtained well before the commencement of work.
7. All the Safety Rules as per the Factory Act 1948, Puducherry Factory Rule and PPCL Safety instructions to be strictly followed inside the plant area.
8. In case of any faulty workmanship in the scope of work, the tenderer must rectify the same. Otherwise the estimated amount will be deducted in your work bill.
9. Our GSTIN No.: 34AAACP6507E1ZS registered with Commercial Taxes Department, Puducherry.
10. Sealed quotation should be super scribed as QUOTATION / ENQUIRY NO. AB-062 "Replacement Work of Cooling Tower Fan 1 & 2 FRP support structures during the Annual maintenance DUE ON: 29.10.2024".
11. Applicable other charges, if any should be clearly mentioned as whether inclusive or exclusive. If not mentioned, it will be presumed that the rate quoted is inclusive of all taxes other charges.
12. The party should submit two copies of photographs of all the employees deployed in PPCL for the above work for gate pass purpose. The name & photo of the employees should be attested by the contractor.
13. The undersigned reserves all rights to accept/reject any or all the quotations without assigning any reasons thereof.
14. The work should be completed within 07 days from the commencement of work till completion of work during shutdown. The mobilization time of one week shall be given. Prefabrication related works and scaffolding works permitted before and after shutdown.
15. The work should not be sub-let. Sub-contracting not permitted.


08/10/2024
EXECUTIVE ENGINEER (MECH)-PLANT



PUDUCHERRY POWER CORPORATION LIMITED
(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)
T.R. PATTINAM - 609606, KARAIKAL.



Phone No:04368- 233060

E-Mail : ppclmmc@gmail.com

Fax: 04368 - 233355.

Our GSTIN No.: 34AAACP6507E1ZS

Ref. No: AB-062/MMC/2024-25/ 1244

Dt. 07.10.2024

ENQUIRY PAGE NO. 3

COOLING TOWER FAN 1 & 2 FRP SUPPORT STRUCTURES REPLACEMENT WORK DURING THE ANNUAL MAINTENANCE SHUTDOWN FOR THE YEAR 2024-25

Sl.No.	Description	Amount in Rs.
1	Cooling Tower Fan 1 & 2 support structures replacement work (Scope of work as per the annexure enclosed -Page 04)	
	Gross Total Amount in Rs.	
	Transportation, Accommodation, Boarding and EPF & ESI Charges	Inclusive
	Sub Total	
	GST @ 18%	
	Net Total Amount in Rs.	
	(Rupees	

Payment Terms: As per Terms & Condition - 2

Validity: 90 days

Note: 1) The rates to be quoted in all the columns of the above schedule and no columns should be left blank, if any column is left blank then the offered quotation will not be considered.

2) The quoted schedule should be affixed by the company seal and signed by the concerned authority.

Name of the Company:

Company seal with Signature:

ANNEXURE


COOLING TOWER FAN 1 & 2 FRP SUPPORT STEEL/STRUCTURES REPLACEMENT WORK

Contractor scope of work

1. The party should visit the site before quoting the rate.
2. The Contractor should take care of their staff safety. Necessary PPE's should be arranged by the Contractor for their staff .
3. At least two days before the shutdown of the unit, the Contractor has to mobilize their manpower, tools and tackles for installation.
4. Existing 12 numbers of 100X50mm old channels removing by breaking their bottom old concrete one by one without disturbing the FRP hood as identified by Engineer In Charge.
5. New same size GI channel 100X50 along with support GI 50X50 angles to be fabricated as per the existing system. Its foot base plate to be fabricated and anchor bolts to be provided.
6. Fixing the new fabricated structure with providing concrete base as per the existing size
7. New Concrete foot foundation 12 numbers (Concrete ratio 1:2:4) to be provided about 450mm length X450 mm width X 450mm height in all newly erected structures.
8. All Civil works including concrete & drilling are contractor scope
9. Necessary scaffolding materials and sufficient labour are to be arranged by the contractor so as to complete the entire work on stipulated period.
10. If FRP Hood which are removed for during installation, to be reinstalled without damage.
11. Welding machines, Welding rods (Adore make only), welding cables, Power cables, Cutting sets & Gas cylinders, Concrete breaking tools and paints are to be arranged by the contractor.
12. Wherever necessary, welding and gas cutting works at position is to be carried out without disturbing the existing system. Welding machine (2 Ph. / 3 Ph.)/ Generators / rectifiers only permitted for all welding works.
13. After curing the concrete, cement-plastering around the concrete to be carried out.
14. Supply and application of IS approved brand epoxy (Grey color) paints of two coats each (primer and finish) over the surface of structure by air or air less spray gun.
15. Contractor shall make its own arrangements for tools and Tackles, Consumables, Welding rods (Adore make only allowed), paint and other rigging material like scaffolding required for the job.
16. The installation work should be completed within 07 days during shutdown.
17. After completion of work all the scrap materials should be shifted to scrap yard as per the instruction of Engineer in-charge.

PPCL Scope of work

1. Necessary steel structures, plate, bolts and nuts will be supplied by PPCL.
2. Air, Water and Power will be provided by PPCL.


08/10/2024
EXECUTIVE ENGINEER (MECH)-PLANT