



PUDUCHERRY POWER CORPORATION LIMITED

(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

PROJECT OFFICE, T.R. PATTINAM 609 606, KARAIKAL.

Email: ppcl.kkl@nic.in

Phone: 04368-233060, 233988

Telefax: 04368-233287

No: F-102/PPCL/EE(M)/AE(Civil)/QN/2025-26/647


Date: 10/07/2025

FIFTH DUE DATE EXTENSION QUOTATION NOTICE

Fourth Due Date Extension Quotation Notice No: F-102/PPCL/EE(M)/AE(Civil)/QN/2025-26 /477 dated: 11/06/2025 for the work of "Repair works to Over Head Tank A1 and C3 block inside the Residential complex at T.R.Pattinam, Karaikal." has been postponed as under:

Details	As Existing	As Revised
Sealed quotations are invited for the above said work by the undersigned from the Contractor and		
will be received upto 3.30 P.M on	9/07/2025	07/08/2025
and will be opened at 4.00 P.M on	10/07/2025	08/08/2025

All the other terms and conditions remain unaltered. The details may be referred in the Quotation Notice which is enclosed herewith and also further details see at <http://ppclgov.in>


10/07/2025

EXECUTIVE ENGINEER (MECH) Plant



PPCL PUDUCHERRY POWER CORPORATION LIMITED

(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

PROJECT OFFICE, T.R. PATTINAM 609 606, KARAIKAL.



No. F-102/PPCL/EE(M)/AE(Civil)/QN/2024-25/ 2117

Date: .02.2025

QUOTATION NOTICE

Sealed quotations are invited for the work of **“Repair works to Over Head Tank A1 and C3 block inside the Residential complex at T.R.Pattinam, Karaikal.”** by the under signed from the Contractor and will be received upto 3.30 P.M on 24/03/2025 and will be opened at 4.00 P.M on 25/03/2025.

Eligibility criteria:

The contractor/firm should submit

- i) the copy of GST registration certificate
- ii) the documentary evidence in support of their own ESI & EPF Code,

Quotations should be in a sealed cover, duly super-scribed as the **“Repair works to Over Head Tank A1 and C3 block inside the Residential complex at T.R.Pattinam, Karaikal.”**

The contractors shall submit the Tender Schedule in Two envelopes sealed in a single cover. The first envelope shall be placed, with EMD in the prescribed format, definite proof for independent code number for ESI, EPF & GST certificate, and the envelope shall be super-scribed as “EMD/pre-qualification documents” and the other envelope shall be super scribed as price Schedule wherein the duly filled schedule shall be placed and sealed.

On the scheduled date of opening, the cover super-scribing “ EMD & pre-qualification documents” definite proof for independent code number for ESI, EPF & GST” and EMD shall be opened. At the time of opening of the Quotation if any contractor fails to furnish related shortfall documents necessary time frame of one week will be given to the tenderers, to furnish the documents, with a condition that, the documents must be to the pre-existed and not the post – existed, failing which their Quotation will be rejected.

EMD Clause:


The Earnest Money for an amount of **Rs. 2150/-** Should be deposited by Bankers cheque / Fixed Deposit receipts / Demand Draft of a Scheduled bank and submitted ~~alongwith~~ the schedule. The Earnest money should be drawn in favour of the Executive Engineer (Mech), PPCL, T.R.Pattinam, payable at Karaikal. At the time of opening of the Quotation if any contractor fails to furnish EMD their Quotation will be rejected.



PUDUCHERRY POWER CORPORATION LIMITED

(A GOVERNMENT OF PUDUCHERRY UNDERTAKING)

PROJECT OFFICE, T.R. PATTINAM 609 606, KARAIKAL.



No. E-102/PPCL/EE(M)/AE(Civil)/QN/2024-25/ 247

Date: .1.2025

Terms & Conditions:-

Quotations should be in a sealed cover, duly super-scribed as the **"Repair works to Over Head Tank A1 and C3 block inside the Residential complex at T.R.Pattinam, Karaikal."** The quotation to be sealed and brought to PPCL, T.R.Pattinam, Karaikal for placing in the Tender Box. The tender box is kept in PPCL, T.R.Pattinam, Karaikal, for dropping of quotation.

1. The rate to be quoted should be inclusive of material charges, labour charges, ESI & EPF & GST contributions, and other inputs involved in the execution of work.
2. The decision of the Engineer in charge shall be final and binding on the successful quotationer.
3. The quotation shall remain valid for a period of Ninety (90) days from the date of opening for acceptance.
4. If the date of opening of the quotation becomes holiday, then the same will be opened on the next working day.
5. The quantity mentioned in the schedule is tentative.
6. The above payments are to be made by the contractor at his cost and it shall be the sole responsibility of the contractor to cover his workers under these provisions and no extra payment whatsoever would be made in this regard.
7. Payment will be released to the contractor within fifteen days from the date of submission of bills/invoice through A/c payee cheque only. Income tax and other taxes wherever applicable will be deducted from payments.
8. The total duration of the contract shall be for a period of one (1) month.
9. If any of the personnel employed by the contractor is found to indulge in acts, subversive of discipline, the same will be brought to the knowledge of the contractor and he shall arrange for replacement of such personnel.
10. The contractor shall indemnify the company from the all liabilities arising out of deployment of personnel by the contractor under various statutory provisions and other issues related thereto
11. The contractor shall furnish the list of persons to be deployed by him. He shall not engage persons below 18 years of age.
12. If the services of the contractor are found to be unsatisfactory during the stipulated contract period and for any other reasons, Engineer - in -charge reserves the right to pre-close the contract without assigning any reasons, whatsoever, however, the contract would be terminated by giving one - month notice.
13. The rate to be quoted shall include all incidental expenses/ESI &EPF&GST Act, Margin of profit etc.,
14. The company will not provide any transport /canteen facilities to the workers to be employed by the contractor and the contractor shall make necessary arrangements in this regard at his own cost.
15. All statutory laws relating to Factory to be complied with by the lowest tenderer.
16. The contractor is informed to inspect the site conditions before quoting his rates.
17. The contractor is liable for damages, defects during contract period.
18. Tools & Tackles to carry out the work shall be supplied by the contractor only.
19. Any damage that would be occurred to the property of PPCL during the time of operation of the work, the contractor has to rectify the same at his own cost.
20. The quotation will be rejected if the contractor failed to meet the terms and conditions of the quotation notice.
21. The undersigned reserves the right to accept /reject any or all the quotations without assigning any reasons thereof.

22. The contractor shall comply with all statutory provision with regard to the persons engaged by him, such as Employee's Provident Fund Act & ESI Act, Minimum Wages Act, contractor labour Act etc. During the period of contract / completion of the contract, all benefits due to the workers deployed by the contractor under various statutory provisions shall be paid by the contractor.
23. Without prejudice to any of the rights or remedies under this contract if the contractor is not able to execute the works due to unavoidable genuine reasons and beyond his control the Executive Engineer (mech) on behalf of the PPCL shall have the option of terminating the contractor without compensation to the contractor.
24. During the course of contract period, deduction of "CESS" to provide social security and various welfare benefits through the Puducherry Buildings and other construction workers Welfare Board under Section 18 of the Building and Other Construction Workers Cess collection (RECS) Act, 1996, shall be made at the rate of 1% (One Percent) of the gross amount of each bill or as per the advice of the Government of Puducherry.
25. The contractor has to sign the documents of terms and condition of the quotation notice for acceptance
26. The undersigned reserves the right to accept / reject any or all the quotations without assigning any reasons thereof.

Special Conditions:

1. All work is covered under Puducherry Goods and Services Act 2017 and hence the contractors are requested to quote the rates including the effect of GST. Additional/ separate claim for any recovery on GST will NOT be entertained on any account after the award of work. The payment is also liable for TDS as instructed by the Commercial Tax Department based on GST.
2. "The Contractor /Service provider shall mandatorily furnish the following documents to the Commissioner, Commercial Tax:
 - i. Copy of the work order.
 - ii. HSN¹ Code of Goods and Service Accounts code of Services which shall be supplied during the execution of the Contract.
 - iii. GST Rate at which the GST would be paid to the commercial Tax Department against each of the items in (ii) above.
3. The information shall be submitted to the Commissioner, Commercial Tax , with a copy to the Procuring/Government Entity, within 15 calendar days of receipt of the Work Order."

Terms & conditions with respect to ESI & EPF and Payment.


1. This work is covered under ESI & EPF Act, and it is responsibility of the contractor to ensure compliance of ESI and EPF norms. Hence the contractors are requested to quote the rates including the effect of ESI & EPF. Additional/Separate claim for ESI & EPF will not be entertained on any account after the award of work.
2. The contractor should have independent code number for ESI & EPF and the contractor shall make pay make payment for ESI & EPF iin own code number other than PPCL code. No permission shall be given for PPCL code.
3. **PAYMENT: 100 %** Payment for the completed work will be made within 30 days for the running bills as well as final bill after submission of ESI&EPF etc. documents.
4. Payment will be made only after submission of the following.
 - **For EPF:**
To be generated from the EPF website for the specific month for the manpower deployed to PPCL and the same to be enclosed separately with a covering letter.
 - i. Combined challan of account no.01, 02, 10, 21 & 22 with TRRN number.
 - ii. EPF - Electronic challan cum Return (ECR).
 - iii. EPF Challan summery / EPF- TTRN details.

• For ESI:

To be generated from the ESI website for the specific month for the manpower deployed to PPCL and the same to be enclosed with a covering letter.

- i. ESI challan number
- ii. ESI monthly contribution – online challan status (Transaction details)
- iii. ESI monthly contribution (Contractor wise) for the month of.....

5. Party should obtain all permits and licenses under the laws or regulations applicable and in connection with the work carried out and shall comply with and discharge all statutory obligations/liabilities under the various laws such as Factory Act/Workmen's Compensation Act/ Employee's State Insurance Act/ Employee's Provident Fund Act / Payment of Wages Act/Contract labour (Regulation & Abolition) Act/ Minimum Wages Act etc., or any modification thereof.


26/05/2025
EXECUTIVE ENGINEER (Mech) Plant

To, The Notice Board,

Copy submitted to:

1. The District Collector, Karaikal- cum The Managing Director, PPCL, Karaikal
2. The Superintending Engineer, PWD, Karaikal.

For favour of
kind information

Copy to:

3. The Regional Publicity Officer, Karaikal.
4. The Executive Engineer (I & PH), PWD, Karaikal.
5. The Executive Engineer, Karaikal Municipality, Karaikal.
6. The Commissioner, T.R. Pattinam,
T.R. Pattinam Commune Panchayat Office.

With a request to display
in the Notice Board


No. F-102/PPCL/EE(M)/AE(Civil)/QN/2024-25/ 2117

Date: .1.2025

PRICE SCHEDULE

Sl. No	Description of Items	Qty	Unit	Rate	Amount
1	Non - RSR Removal of OHT sintex tank (2Nos) each having a capacity of 1000 liters from the elevated floor 3 level by necessary scaffolding/ ladder arrangements and refix the same. (i) Including demolishing the lime concrete with Mangalore pressed tiles manually and disposal of material within 50meter lead.(ii) applying a slurry coat of neat cement using 2.75kg/sqm of cement admixed with water proofing compound confirming to IS:2645 and approved over the RCC slab including adjoining walls up to 300mm height including cleaning the surface before treatment. (iii) Providing and laying of cement concrete 1:1.5:3 flooring at the tank bottom including rounding of walls and slabs etc, complete as directed by the Engineer in charge.	2	job		
2	Code No: 14.72 Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story height made with 40 mm dia .M.S.tube 1.5m centre to centre , horizontal & vertical tubes joining with cup & lock system with M.S.tubes, M.S.tube challies, M.S. clamps and M.S.staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as approved. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. (Note: This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done.)	50	Sqm		
3	Code No: 26.28.3 Chipping of unsound / weak concrete material from slabs , beams , columns etc. with manual Chisel and / or by standard power driven percussion type or of approved make including tapering of all edges , making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-in charge - 25 mm average thickness	10	Sqm		
4	Code No: 26.31.2 Providing , mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per pacifications and direction complete in all respect - Epoxy bonding adhesive having coverage 2.20 sqm /kg of approved make	10	Sqm		

5	Code No: 26.32.2 Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded fine aggregate with polymer minimum 2% by wt. of cement used) as per specifications and direction. Note: Measurement and Payment : The Pre- measurement of thickness shall be done just after the surface preparation is completed and payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and / or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N / Sqmm) - 25 mm average thickness in two layers	10	Sqm		
6	Code No: 18.7.3 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in charge - internal work - exposed on wall - 25mm nominal dia pipes	12	meter		
7	Code No: 18.7.5 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in charge - internal work - exposed on wall - 40mm nominal dia pipes	54	meter		
				Total	


 25/05/2025
 EXECUTIVE ENGINEER (Mech) Plant